

# GENERATORS MOD SHOP

METAL MASTERS 23701 US HWY 76 NEWBERRY SC 29108 803-276-6403

2019 Price List

## New Items:

**Breakers** - Schneider "Square D" Breakers, Square D and ABB LSI Trip  
**Load banks** - Roof Mount & Standalone, Extended Enclosure maintaining Vertical air flow and DBA levels  
**Fuel Cleaning "Polishing" Systems**, Annunciators UL NGR  
**SE-701, I/O Module, LED Lights, Enclosure Painting "RAL/PPG"**  
**GENERATOR STORAGE** and Shipping assistance

## TABLE OF CONTENTS

**CONTROL ITEMS:** Batteries, Chargers, Backup Battery System, GFR, Emer Stop, Lights,  
Load Centers, Transformers, Heaters, Crankcase "CCV", Racor Fuel Filters, Coolant Overflow

**BREAKERS AND ACCESSORIES:** ABB & Schneider "Square D", Voltage Changes

**LOUVERS, CAM LOCKS, TESTING, FUEL SPILL PREVENTION:** Spill Bucket, OPV Fill, Drop Tube, OPV Solenoid  
Local Fuel Fill Annunciator, Vent Extensions, FUEL CLEANING/POLISHING SYSTEM,  
DAY TANK Conversion for factory Base Tanks, SERVICE PLATFORMS "OSHA", PAINT - Encl/Tank

**LOAD BANKS:** Radiator, Roof, Standalone, (IBC, Seismic, DBA considerations) SILENCERS, DIESEL PARTICULATE FILTERS

**FUEL TANKS (UL and ULC)**

**TRAILERS WITH FUEL TANKS**

**PDI - PIQ, "Predelivery Inspection - Partner in Quality", Provided at no cost with testing.**

**STORAGE AND ASSOCIATED GENERATOR SERVICES**

## Notes:

**Lead Times.** Completion dates are normally 2-6 weeks after the start date. Start dates are scheduled with a released purchase order, when the generator and parts are received.

**Shipping costs.** Shipping assistance is available. The "Shipping" tab has rates for standard loads. Non-standard loads, oversize or requiring drop deck, double drop, hot shot or other request is as follows: Shipping to and from the Modification Shop is the responsibility of others.

**Warranty Process:** 1. Report and discuss issue with "Hot Desk", Call 803-276-6403ext111 or 864-415-8314. Parts normally match the generator warranty. Installation is covered by Metal Masters for 2 years.

**Code compliance.** All items will comply with the National US and Canadian codes. State, County, City, local or other code is the responsibility of others. Providing data sheets, drawings, photos and discussion with the Mod Shop will normally resolve compliance issues.

**Specifications and/or Drawings.** Is the responsibility of others.

The Mod Shop will provide notification of any changes, deviations or exceptions

**Order Cancellations.** Cancel at any time, however will be responsible for 100% of the cost of items purchased and received, labor and any other costs to Metal Masters. In most cases early cancellations have no cost.

**Dealer Ordered Parts/equipment.** Provided items must be identified when requesting a quote.

We do our best to meet customer completion dates however are not guaranteed.

			(Note: Generators not listed or outside the range contact Metal Masters)			
			(Option is available unless marked "X")			
			Diesel 250-2000kW	Diesel 30 - 200kW	NAT/LP Gas 30 - 150	NAT/LP Gas 175 - 300
		NOTE:	(24VDC)	(12VDC)	(12VDC)	(24VDC)
<b>BEST BATTERY SYSTEM "REDUNDANT" / BATTERIES AND OTHER:</b>						
SENS Best Battery Switch BBS 4800 (>1000kW)	Installed	\$4,800.00			X	
SENS Best Battery Switch BBS 1600 (< 1000kW)	Installed	\$3,400.00			X	
Battery Charger SENS NRG22-10-RC 10A 12/24VDC,120-208-240V	Installed	\$975.00				
Battery Charger SENS NRG22-20-RCLS 20A 12/24VDC,120-208-240V	Installed	\$1,304.00			X	
Battery (12VDC For Compact) includes: cables & rack	Installed	\$550.00				
Battery (24VDC, Qty 2) includes: cables & rack	Installed	\$800.00			X	
Battery (24VDC, Qty 2) includes: cables & rack	Installed	\$1,200.00			X	
Battery Disconnect Switch	Installed	\$846.00				
<b>Note: Generators normally come with one battery charger and one battery. For a complete system you will need the BBS Switch, (1) additional charger and battery(s)</b>						
<b>CONTROL PANEL: GFA, EMER STOP</b>						
Gnd Fault Alarm Relay SE-701 (CT required / Pickup 1-99%)	Installed	\$1,484.00				
Gnd Fault Alarm Relay PGR4300 (CT not required / Pickup 100A 1200A)	Installed	\$1,543.00				
Emergency Stop / External	Installed	\$550.00				
<b>ELECTRONIC: Lights, Load Centers, Transformers</b>						
Interior AC Lights, convenience receptacle & on/off switch (Qty 2)	Installed	\$530.00				
Exterior AC LED Flood Lights, convenience receptacle & on/off switch (Qty 2)	Installed	\$750.00				
Interior DC Lights "Hallogen" CAT (Qty 2) with off/on timer (fused)	Installed	\$530.00				
GFCI Receptacle Nema 3R with Cover (duplex)	Installed	\$350.00				
100A 1P Load Center (N3R 12sp panel with Main)	Installed	\$570.00			X	
100A 1P CSA Load Center (N3R 12sp panel with Main)	Installed	\$750.00			X	
125A 1P Load Center (N3R 24sp panel with Main)	Installed	\$650.00			X	
125A 1P CSA Load Center (N3R 24sp panel with Main)	Installed	\$950.00			X	
150A 1P Load Center (N3R 24sp panel with Main)	Installed	\$750.00			X	
15kVA Transformer (480 Primary to 120/240 Secondary)	Installed	\$1,512.00			X	
7kVA Transformer (480 Primary to 120/240 Secondary)	Installed	\$1,100.00			X	
<b>HEATERS: Battery, Enclosure, Lube Oil</b>						
Battery Heater 120V One Battery 12VDC System	Installed	\$665.00	X			X
Battery Heaters 120V Two Battery 24VDC System	Installed	\$850.00		X	X	
Battery Heaters 120V (Two 4D batteries)	Installed	\$1,465.00		X	X	
Battery Heaters 120V (Four 4D batteries)	Installed	\$2,200.00		X	X	X
Enclosure Heater 1-2kW	Installed	\$650.00				
Enclosure Heater "BERKO HUHAA524 3.7-5kW (C9 - C32)	Installed	\$1,300.00		X	X	
Lube Oil Sump Heater Pad small 120V (100-150Watts)	Installed	\$565.00	X			X
Lube Oil Sump Heater Pad large 120V (250-400Watts)	Installed	\$765.00		X	X	
<b>FUEL: CCV and Racor Fuel Filters</b>						
Crankcase Ventilation Filter (Racor/Parker 4500)	Installed	\$900.00			X	X
Crankcase Ventilation Filter (Racor/Parker 6000)	Installed	\$1,200.00			X	X
Crankcase Ventilation Filter (Racor/Parker 8000)	Installed	\$1,400.00			X	X
Crankcase Ventilation Filter (Racor/Parker (QTY2) 6000)	Installed	\$2,400.00			X	X
Crankcase Ventilation Filter (Racor/Parker (QTY2) 8000)	Installed	\$3,200.00			X	X
<b>(Note: Not closed loop)</b>						
Racor Fuel Filter / Water Sep 500FG-10 (Single)	Installed	\$1,200.00	X		X	X
Racor Fuel Filter / Water Sep 900FH-10 (Single)	Installed	\$1,400.00	X		X	X
Racor Fuel Filter / Water Sep 1000FH-10 (Single)	Installed	\$1,600.00			X	X
Racor Fuel Filter / Water Sep RA75/1000FHX-10 (Double)	Installed	\$2,800.00		X	X	X
Racor Fuel Filter / Water Sep RA79/1000FHV-10 (Triple)	Installed	\$3,200.00		X	X	X
<b>Other:</b>						
Coolant Overflow Container	Installed	\$210.00				



<b>IF YOU DON'T SEE YOUR ITEM CALL or email TERRY DESPARD 864-415-8314 tdespard@gmail.com</b>						
(*) Kit Available , (**) Available for Lean Design						
<b>*LOUVERS - Motorized Intake - Gravity Discharge</b>						
	Pricing					KIT
40kW - 100kW	\$2,600.00					\$2,200.00
125kW - 200kW	\$2800.00					\$2,400.00
250kW - 450kW	\$3200.00					\$2,800.00/\$2400.00
500kW - 650kW	\$4200.00					\$3,800.00/\$3400.00
700kW - 1000kW	\$5100.00					
AC available any model						
24VDC available on 24VDC Models						
Note: A Single Phase 100A Load Center is provided at no cost with AC louvers only when other AC items are ordered. Lights, receptacles, heaters, etc.						
<b>*CAM LOCKS - Box or Flush Mount (for any model)</b>						
	Any Model	(NO NEUTRAL)				Kit
400A (5 cam locks)	\$1,200.00	\$1,100.00				\$1,000.00
800A (10 cam locks)	\$2,400.00	\$2,200.00				\$1,500.00
1200A (15 cam locks)	\$3,600.00	\$3,300.00				\$2,000.00
1600A (20 cam locks)	\$4,800.00	\$4,200.00				\$3,000.00
Installation or Kit includes: Flush Mount plate or box , Female Cam Locks, protective covers, wired or wire for kit. Neutral not provided for load banks.						
<b>TESTING - Load bank (Call for Quote)</b>						
<b>*FUEL SPILL PREVENTION/ Extended Vent Piping/ Fuel Cleaning Systems</b>						
<b>FUEL SPILL PREVENTION - Any kW or Model Generator:</b>		<b>40kW - 200kW</b>	<b>250kW- 650kW</b>	<b>700kW- 1000kW</b>		<b>KIT 12/24VDC/120VAC</b>
5 gallon Fill Spill bucket located inside or outside the enclosure		\$750.00	\$750.00	\$750.00		\$600.00
7 gallon Fill Spill bucket located inside or outside the enclosure		\$800.00	\$800.00	\$800.00		\$650.00
OPV Valve with Drop Tube Adapter		\$1,400.00	\$1,400.00	\$1,400.00		\$1,200.00
Drop Tube Extension (any tank up to 48" deep)		\$400.00	\$400.00	\$400.00		\$200.00
Electronic Fuel Overfill Solenoid set @ 95% to operate with Crit High Alarm		\$1,600.00	\$1,600.00	\$1,600.00		\$1,600.00
Local Annunciator (UL)(N3R) 2 light (with High and Critical High alarms, operates solenoid valve if ordered)		\$800.00	\$800.00	\$800.00		\$1,000.00
Local Annunciator (UL)(N3R) 5 light (Crit Low,Low,High,Crit High, leak detect operates solenoid valve if ordered)		\$1,200.00	\$1,200.00	\$1,200.00		\$1,200.00
Floats for Annunciator and/or Overfill valve operation (2 or 4 float assembly)		\$450.00	\$450.00	\$450.00		\$300.00
4-20 ma Sender (wired to local control panel) - programming by others		\$650.00	\$650.00	\$650.00		
(Note: Factory tanks must have (1) spare port for floats. Tanks H14" or less must have (2) spare ports)						
<b>EXTENDED VENT PIPING</b>		<b>40kW - 200kW</b>	<b>250kW- 650kW</b>	<b>700kW- 1000kW</b>		
Extend Normal Vent located outside the Enclosure 12ft above grade		\$600.00	\$900.00	\$1,000.00		\$1,000.00
Extend Normal Vent located inside the Enclosure 12ft above grade		\$1,400.00	\$1,400.00	\$1,400.00		
Extend Emergency Vent located outside the Enclosure 12ft above grade		\$1,000.00	\$1,200.00	\$1,600.00		\$1,200.00
Extend Emergency Vent located inside the Enclosure 12ft above grade		\$1,600.00	\$1,800.00	\$2,000.00		
(Note: Extended vents inside the enclosure may require 45-90deg bends. Options for pipe routing will be discussed with the dealer prior to installation)						
<b>FUEL CLEANING SYSTEMS "FM Approved/Listed NFPA 20,25, 110</b>	<b>600gal or less</b>	<b>601-5000gal</b>	<b>5001-15000gal</b>			
FTI 1.5 (Tanks up to 600gal)	\$7,900.00					\$7,900.00
FTI 2.8 (Tanks up to 5000gal)		\$8,400.00				\$8,400.00
FTI 5A (Tanks up to 15000gal)			\$18,500.00			\$18,500.00
SIZING "FTI" is based on Fuel Tank size						
<b>*Day Tank Conversions for Base Tanks</b>						
(Any Generator - Skid , Weatherproof or Sound Attenuated)						
<b>Size - kW or Model Generator:</b>		<b>40kW - 200kW</b>	<b>250kW- 650kW</b>	<b>700kW- 1000kW</b>		<b>Kit</b>
Mounting on Baseframe or Tank		\$800.00	\$800.00	\$800.00		\$600.00
PRYCO - Pump and Indication System (pumps sized for generator)		\$3,200.00	\$3,200.00	\$3,200.00		\$3,000.00
Base tank floats - operate pumps, indication at pump controller		\$360.00	\$360.00	\$360.00		\$300.00
Hoses, wiring, labor, testing (kit has hoses/fittings only)		\$500.00	\$500.00	\$500.00		\$200.00
(Note: Tanks provided by others must have (4) spare 2" NPT fittings)						
<b>Total Kit Price</b>	\$0.00	\$4,860.00	\$4,860.00	\$4,860.00		\$4,100.00
Note: Check tank needing conversion for spare NPT fitting						
<b>**Platforms - Generator Service "OSHA Approved"</b>						
(Packaged to ship loose with Generator on the same truck)						
BUILD YOUR OWN "MODULAR"						
(1) 4x4 Modular Section with hand rails	\$1100.00					
(1) Set of Stairs (standard stairs sized for your platform height)	\$1200.00					
"MADE TO FIT"						
Single Side Access	\$2,400.00	\$3,000.00	\$3400.00	\$4200.00		\$5200.00
Dual Side Access	\$4,800.00	\$5,800.00	\$6400.00	\$7600.00		\$9200.00
U Shaped Platform	\$6,000.00	\$6,600.00	\$7400.00	\$9200.00		\$10800.00
Notes: Assembly required.						
Prices include Shipping to Newberry to ship with the generator or any location within 500miles of Newberry SC.						
<b>PAINT Enclosures (RAL or PPG Colors)</b>						
<b>Size - kW or Model Generator:</b>		<b>30kw-200kW</b>	<b>250kw</b>	<b>300kW-650kW</b>	<b>700kw-1000kW</b>	
Enclosure (Outside and door jams)	\$1,900.00	\$3,200.00	\$4,200.00	\$6,800.00		
Replace Decals	\$250.00	\$400.00	\$500.00	\$600.00		
Paint Fuel Tank (same color as enclosure/ any size up to 96hr)	\$600.00	\$800.00	\$1,000.00	\$1,600.00		
Corrosion Resistant Protection " Paint" "Undercoating"	\$3,300.00	\$4,200.00	\$6,800.00	\$8,800.00		
(Process - Decals, doors removed, surface is prepped to accept new paint, outside, door jams and other visible areas are painted)						
<b>NOTE: POWERCOAT PAINTING AVAILABLE FOR ANY METAL ONLY ITEM COMPACT SIZE OR SMALLER</b>						

GENERATOR - 208 or 480, Open, WX, SA					RADIATOR MOUNTED							ROOF MOUNTED		STAND ALONE		AUTO LOAD LEVELING		DPF "Diesel Particulate Filter"											
MODEL	Genet kW	Voltage	Phase	Load Bank Size	OPEN (No Enclosure)		Weatherproof		Sound Attenuated		ROOF MOUNTED		STAND ALONE		AUTO LOAD LEVELING		DPF "Diesel Particulate Filter"												
					Price	Option	Price	Option	Price	Option	Price	Option	Price	Option	Option	Price	Option	Price	Option										
					Load Bank	Outdoor rating	Load Bank Outdoor Rated	Sound Attenuating Foam	LOAD BANK TURN DUCT	LOAD BANK Outdoor Rated	SILENCER (See Critical Roof Mounted Carbon Steel)	Extended Enclosure	Load Bank Outdoor Rated	Load Bank Outdoor Rated	Option	Miratch Passive DPF Roof Mount	WX & SA Enclosures	Price	Option										
<b>VOLTAGE 208</b> <small>If the combination your looking for is not listed use next larger or split the \$ amount between the two closest</small>					<small>Manufacturers: Load Bank Direct, Avtron</small>		<small>Manufacturers: Load Bank Direct, Avtron</small>		<small>For Vertical Air Flow (Not an Exit Enclosure)</small>		<small>Manufacturers: Avtron, Delta, EA</small>		<small>Manufacturers: LOAD BANK DIRECT</small>		<small>Manufacturers: AVTRON</small>		<small>Available on All Sets</small>		<small>Manufacturers: Miratch</small>		<small>Horizontal Air Flow unless "Extended Enclosure" Option is selected</small>		<small>Black Carbon Steel (Stainless available - request a quote)</small>		<small>Commissioning</small>				
40	208	3	20	\$5,100.00	\$765.00	\$6,500.00	\$1,200.00	\$800.00	\$7,500.00	\$1,500.00	\$2,000.00	\$6,800.00	\$7,500.00	\$1,200.00	LTR 2	\$7,100.00	\$1,200.00												
50	208	3	25	\$5,100.00	\$765.00	\$6,500.00	\$1,200.00	\$800.00	\$7,500.00	\$1,500.00	\$2,000.00	\$6,800.00	\$7,500.00	\$1,200.00	LTR 2	\$7,100.00	\$1,200.00												
60	208	3	30	\$5,100.00	\$765.00	\$6,500.00	\$1,200.00	\$800.00	\$7,500.00	\$1,500.00	\$2,000.00	\$6,800.00	\$7,500.00	\$1,200.00	LTR 2	\$7,100.00	\$1,200.00												
80	208	3	40	\$5,100.00	\$765.00	\$6,500.00	\$1,200.00	\$800.00	\$7,500.00	\$1,500.00	\$2,000.00	\$6,800.00	\$7,500.00	\$1,200.00	LTR 2	\$7,100.00	\$1,200.00												
100	208	3	50	\$5,100.00	\$765.00	\$6,500.00	\$1,200.00	\$800.00	\$7,500.00	\$1,500.00	\$2,000.00	\$6,800.00	\$7,500.00	\$1,200.00	LTR 4	\$12,500.00	\$1,200.00												
125	208	3	65	\$6,000.00	\$825.00	\$7,000.00	\$1,400.00	\$800.00	\$8,000.00	\$1,800.00	\$2,000.00	\$7,300.00	\$8,000.00	\$1,200.00	LTR 4	\$12,500.00	\$1,200.00												
150	208	3	75	\$6,100.00	\$825.00	\$7,100.00	\$1,400.00	\$800.00	\$8,100.00	\$1,800.00	\$2,000.00	\$7,400.00	\$8,100.00	\$1,200.00	LTR 4	\$12,500.00	\$1,200.00												
175	208	3	90	\$6,400.00	\$825.00	\$7,400.00	\$1,400.00	\$800.00	\$8,400.00	\$1,800.00	\$2,000.00	\$7,700.00	\$8,400.00	\$1,200.00	LTR 4	\$12,500.00	\$1,200.00												
200	208	3	100	\$6,500.00	\$825.00	\$7,500.00	\$1,400.00	\$800.00	\$8,500.00	\$1,800.00	\$2,000.00	\$7,800.00	\$8,500.00	\$1,200.00	LTR 4	\$12,500.00	\$1,200.00												
250	208	3	125	\$6,800.00	\$825.00	\$7,800.00	\$1,200.00	\$800.00	\$8,800.00	\$2,400.00	\$3,000.00	\$8,100.00	\$8,800.00	\$1,200.00	LTR 9-6	\$17,500.00	\$1,200.00												
300	208	3	150	\$7,100.00	\$825.00	\$8,100.00	\$1,200.00	\$800.00	\$9,100.00	\$2,400.00	\$3,000.00	\$8,400.00	\$9,100.00	\$1,200.00	LTR 9-6	\$17,500.00	\$1,200.00												
350	208	3	175	\$7,400.00	\$825.00	\$8,400.00	\$1,200.00	\$800.00	\$9,400.00	\$2,400.00	\$3,000.00	\$8,700.00	\$9,400.00	\$1,200.00	LTR 12-6	\$21,400.00	\$1,200.00												
400	208	3	200	\$7,700.00	\$825.00	\$8,700.00	\$1,200.00	\$800.00	\$9,700.00	\$2,400.00	\$3,000.00	\$9,000.00	\$9,700.00	\$1,200.00	LTR 15-8	\$25,700.00	\$1,200.00												
450	208	3	225	\$7,800.00	\$825.00	\$8,800.00	\$1,200.00	\$800.00	\$9,800.00	\$2,400.00	\$3,000.00	\$9,100.00	\$9,800.00	\$1,200.00	LTR 15-8	\$25,700.00	\$1,200.00												
500	208	3	250	\$7,900.00	\$825.00	\$8,900.00	\$1,200.00	\$800.00	\$9,900.00	\$2,400.00	\$3,000.00	\$9,200.00	\$9,900.00	\$1,200.00	LTR 15-8	\$25,700.00	\$1,200.00												
<b>VOLTAGE 480</b> <small>If the combination your looking for is not listed use next larger or split the \$ amount between the two closest</small>																													
125	480	3	65	\$5,900.00	\$825.00	\$6,900.00	\$1,400.00	\$800.00	\$7,900.00	\$1,800.00	\$2,000.00	\$7,200.00	\$7,900.00	\$1,200.00	LTR 4	\$12,500.00	\$1,200.00												
150	480	3	75	\$6,000.00	\$825.00	\$7,000.00	\$1,400.00	\$800.00	\$8,000.00	\$1,800.00	\$2,000.00	\$7,300.00	\$8,000.00	\$1,200.00	LTR 4	\$12,500.00	\$1,200.00												
175	480	3	100	\$6,200.00	\$825.00	\$7,200.00	\$1,400.00	\$800.00	\$8,200.00	\$1,800.00	\$2,000.00	\$7,500.00	\$8,200.00	\$1,200.00	LTR 4	\$12,500.00	\$1,200.00												
200	480	3	100	\$6,200.00	\$825.00	\$7,200.00	\$1,400.00	\$800.00	\$8,200.00	\$1,800.00	\$2,000.00	\$7,500.00	\$8,200.00	\$1,200.00	LTR 9-6	\$17,500.00	\$1,200.00												
225	480	3	125	\$6,600.00	\$825.00	\$7,600.00	\$1,200.00	\$800.00	\$8,600.00	\$2,400.00	\$3,000.00	\$7,900.00	\$8,600.00	\$1,200.00	LTR 9-6	\$17,500.00	\$1,200.00												
250	480	3	125	\$6,600.00	\$825.00	\$7,600.00	\$1,200.00	\$800.00	\$8,600.00	\$2,400.00	\$3,000.00	\$7,900.00	\$8,600.00	\$1,200.00	LTR 9-6	\$17,500.00	\$1,200.00												
300	480	3	150	\$6,900.00	\$825.00	\$7,900.00	\$1,200.00	\$800.00	\$8,900.00	\$2,400.00	\$3,000.00	\$8,200.00	\$8,900.00	\$1,200.00	LTR 9-6	\$17,500.00	\$1,200.00												
350	480	3	175	\$7,200.00	\$825.00	\$8,200.00	\$1,200.00	\$800.00	\$9,200.00	\$2,400.00	\$3,000.00	\$8,500.00	\$9,200.00	\$1,200.00	LTR 15-8	\$25,700.00	\$1,200.00												
400	480	3	200	\$7,300.00	\$825.00	\$8,300.00	\$1,200.00	\$800.00	\$9,300.00	\$2,400.00	\$3,000.00	\$8,600.00	\$9,300.00	\$1,200.00	LTR 15-8	\$25,700.00	\$1,200.00												
450	480	3	225	\$7,500.00	\$825.00	\$8,500.00	\$1,200.00	\$800.00	\$9,500.00	\$2,400.00	\$3,000.00	\$8,900.00	\$9,600.00	\$1,200.00	LTR 15-8	\$25,700.00	\$1,200.00												
500	480	3	250	\$7,700.00	\$825.00	\$8,700.00	\$1,200.00	\$800.00	\$9,700.00	\$2,400.00	\$3,000.00	\$9,000.00	\$9,700.00	\$1,200.00	LTR 15-8	\$25,700.00	\$1,200.00												
550	480	3	275	\$7,900.00	\$950.00	\$8,900.00	\$1,200.00	\$800.00	\$9,900.00	\$2,400.00	\$3,000.00	\$9,200.00	\$9,900.00	\$1,200.00	LTR 15-8	\$25,700.00	\$1,200.00												
600	480	3	300	\$8,500.00	\$950.00	\$9,500.00	\$1,200.00	\$800.00	\$10,500.00	\$3,200.00	\$3,000.00	\$9,800.00	\$10,500.00	\$1,200.00	LTR 15-8	\$25,700.00	\$1,200.00												
650	480	3	325	\$9,400.00	\$950.00	NA			\$11,400.00		\$5,000.00	\$12,300.00	\$12,000.00	\$1,200.00	LTR 20-10	\$37,000.00	\$1,500.00												
700	480	3	350	\$9,500.00	\$950.00	NA			\$11,500.00		\$5,000.00	\$12,500.00	\$12,000.00	\$1,200.00	LTR 20-10	\$37,000.00	\$1,500.00												
750	480	3	375	\$9,700.00	\$950.00	NA			\$11,700.00		\$5,000.00	\$12,600.00	\$12,000.00	\$1,200.00	LTR 20-10	\$37,000.00	\$1,500.00												
800	480	3	400	\$9,800.00	\$950.00	NA			\$11,800.00		\$5,000.00	\$13,000.00	\$12,000.00	\$1,200.00	LTR 20-10	\$37,000.00	\$1,500.00												
1000	480	3	500	\$10,700.00	\$950.00	NA			\$12,700.00		\$5,000.00	\$13,500.00	\$12,000.00	\$1,200.00	LTR 30-12	\$49,000.00	\$1,500.00												

**IMPORTANT NOTES:**  
 1. LOAD BANK'S Include: Control Power Transformer, Auto Dump Circuit and Remote Controller (exception - Stand Alone can have a local or remote controller)  
 Not included: Load bank breaker (see breaker tab), Auto Load Leveling and options listed on this sheet

2. DPF's and Silencers Include: All piping, flanges, rain caps, hardware required for a standard installation. Note: DPF's, Silencer's or other items that creates an over height issue will ship loose unless directed by the customer.  
 Note: Customers providing a DPF or Silencer is responsible to provide these same items (Mount Brackets/Cradle, Inlet and Outlet 90deg Flanged elbows, rain cap, nuts/bolts/gaskets)

3. DBA Level Reduction with added options: This level reduction numbers are based on an overall average of different models and options. All models with every option has not been sound tested. A graph showing the estimated reduction is available.  
 WEATHERPROOF SETS: Can expect near factory sound attenuated numbers with Sound Foam and the Turn Duct.



**Sound Enclosure Tanks - UL142 or ULC-S601 (Request a quote for UL2085, IBC, Seismic)**

*If you don't see the generator model/size your looking for, find the gallons needed and closet dimensions.*

*Provide the gallons and dimensions needed. We will have a tank made for your job.*

Generator	Approx. Run Time	Usable Gallons	Length****	Width*	Height	Stub Up	Approximate Tank Dry Weight	Tank Price * ** *** ****
40-60kW	18	100	119	39	10	16	1170	\$ 5,400.00
40-60kW	24	130	119	39	12	16	1250	\$ 6,080.00
40-60kW	36	195	119	39	18	16	1490	\$ 6,160.00
40-60kW	48	255	119	39	22	16	1670	\$ 6,590.00
40-60kW	72	390	119	39	33	16	2140	\$ 7,050.00
40-60kW	96	515	143	39	34	16	2640	\$ 7,930.00
80-100kW	18	145	140	39	11	20	1420	\$ 6,280.00
80-100kW	24	190	140	39	14	20	1560	\$ 6,380.00
80-100kW	36	285	140	39	21	20	1880	\$ 6,790.00
80-100kW	48	375	140	39	27	20	2160	\$ 7,090.00
80-100kW	72	570	162	39	34	20	2850	\$ 8,130.00
80-100kW	96	760	192	39	39	20	3480	\$ 9,430.00
125-200kW	18	260	168	39	16	24	1950	\$ 6,890.00
125-200kW	24	345	168	39	20	24	2180	\$ 7,290.00
125-200kW	36	560	168	39	32	24	2830	\$ 8,430.00
125-200kW	48	750	192	39	36	24	3490	\$ 9,430.00
125-200kW	72	1115	192	60*	32	24	4500	\$ 10,800.00
125-200kW	96	1480	192	71*	35	24	5710	\$ 11,290.00
250-300kW	18	410	194	71	12	45	3160	\$ 9,000.00
250-300kW	24	550	194	71	16	45	3480	\$ 9,200.00
250-300kW	36	820	194	71	24	45	4110	\$ 9,600.00
250-300kW	48	1090	194	71	32	45	4790	\$ 10,000.00
250-300kW	72	1640	228	71	36	45	6080	\$ 10,900.00
250-300kW	96	2180	239	90*	36	45	8200	\$ 12,100.00
320-400kW	18	660	210	71	18	45	3940	\$ 9,860.00
320-400kW	24	880	210	71	22	45	4370	\$ 10,600.00
320-400kW	36	1320	216	71	32	45	5400	\$ 10,800.00
320-400kW	48	1760	242	71	36	45	6560	\$ 11,500.00
320-400kW	60	2200	265	90*	32	45	9960	\$ 12,600.00
320-400kW	72	2640	265	90*	38	45	10850	\$ 13,500.00
350-500kW	18	660	210	71	18	45	3940	\$ 9,860.00
350-500kW	24	880	210	71	22	45	4370	\$ 10,600.00
350-500kW	36	1320	216	71	32	45	5400	\$ 10,800.00
350-500kW	48	1760	242	71	36	45	6560	\$ 11,500.00
350-500kW	60	2200	265	90*	32	45	9960	\$ 12,600.00
350-500kW	72	2640	265	90*	38	45	10850	\$ 13,500.00
550-600kW	18	770	222	71	18	45	4250	\$ 10,360.00
550-600kW	24	1030	228	71	24	45	4890	\$ 10,600.00
550-600kW	36	1540	228	71	34	45	5960	\$ 11,100.00
550-600kW	48	2050	239	90*	34	45	9400	\$ 12,000.00
550-600kW	60	2570	265	90*	36	45	10610	\$ 14,300.00
750-800kW	18	1030	300	82	20	72	7540	\$ 14,100.00
750-800kW	24	1380	300	82	24	72	8280	\$ 14,400.00
750-800kW	36	2060	300	82	36	72	10380	\$ 15,100.00
750-800kW	48	2750	336	82	40	72	12240	\$ 15,800.00

\*Widths over the base skid footprint require 4" rails for mounting (adds 4" to given height). As these are sound attenuated units a sound guard is included in these cases to close off the area between the tank, rails and generator base skid.

\*\*Includes the tank, (2) emergency vents, 2" normal vent, 2" lockable fill, Krueger fuel gauge, suction/return fittings, low level & leak detection switches, a 1/2" rupture basin drain plug and 2 extra 2" NPT fittings. Rails also included as noted depending on width. The "Total Price" also includes the Canadian Requirements.

\*\*\*Canadian Requirements includes top-mounted leak detection switch, high level switch, vent/fill extensions to minimum 36" above pad as required and secondary normal vent in the outer tank.

\*\*\*\*Tank emergency vents, normal vent, fill/spill container and gauge are located outside of the enclosure on the radiator end.

Trailers w/ Double Wall Tanks		Generator Size*				Trailer/Tank Information						Pricing							
Generator	Length	Width	Height	Weight	Tank Cap (Gallons)	Tank Weight	Trailer Model	# of Axles	Trailer GVWR	Trailer Weight	Safety	Total Weight	Base**	Hydraulic Surge Brakes**	2.5/16" Ball Coupler	(2) Rear SABS	(4) Tie Down Rims	Spare Tire	
30kw - 60kw WX and Sound	92	39	62	2880	80	1315	G6	Single	6,800				\$ 6,500.00	\$ 265.00	\$ 56.00	\$ 280.00	\$ 75.00	\$ 250.00	
30kw - 60kw WX and Sound	92	39	62	2880	130	1700	G7	Tandem	7,500				\$ 7,300.00	\$ 265.00	\$ 56.00	\$ 280.00	\$ 75.00	\$ 250.00	
80kw - 100kw WX and Sound	114	39	73	3430	100	1315	G7	Tandem	7,500				\$ 7,100.00	\$ 445.00	\$ 56.00	\$ 280.00	\$ 75.00	\$ 250.00	
80kw - 100kw WX and Sound	114	39	73	3430	200	1700	G10	Tandem	11,000				\$ 9,100.00	\$ 445.00	\$ 56.00	\$ 280.00	\$ 75.00	\$ 250.00	
125kw - 200kw WX and Sound	143	39	73	4600	175	3250	G10	Tandem	11,000				\$ 8,800.00	\$ 505.00	\$ 56.00	\$ 280.00	\$ 75.00	\$ 250.00	
125kw - 200kw WX and Sound	143	39	73	4600	300	3680	GV12	Tandem	13,200				\$ 9,700.00	\$ 505.00	\$ 56.00	\$ 290.00	\$ 75.00	\$ 250.00	
Options:																			
JOB BOX (longue mounted)													\$ 600.00						

\*Generator sizes based on available spec sheets.

\*\*Base trailer price includes 3" Lunette Eye, tongue jack, electric brakes, a smooth steel deck and the listed tank capacity. Options listed are in addition to the base price.

\*\*\*Hydraulic surge brakes would be in place of the electric brakes.

**Date:** \_\_\_\_\_  
**Dealer:** \_\_\_\_\_  
**PO #:** **PODI \$500.00**

**WO#:** \_\_\_\_\_

**EQUIPMENT TYPE:** **Generator**

Genset MFG: _____	Genset Model #: _____	Genset Serial #: _____
Engine MFG: _____	Engine Model #: _____	Engine Serial #: _____
Radiator MFG: _____	Radiator Location: _____	Radiator Group #: _____
Control Panel MFG: _____	Control Panel Model #: _____	Control Panel Serial #: _____
Arrangement #: _____	Service Meter units: _____	Fuel Type: _____
Rated Kilowatts: _____	Rated kV Amps: _____	Rated Phase: _____
Emission Tier: _____	Rated Power Factor: _____	Rated Volts AC: _____

<b>Mod Program Manager</b>	Name: _____	Office Phone #: _____	Cellphone #: _____	Fax #: _____	Email: _____
<b>Lead Technician:</b>	_____	_____	_____	_____	_____
<b>Test Technician:</b>	_____	_____	_____	_____	_____

**Start Date:** \_\_\_\_\_ **Completed Date:** \_\_\_\_\_ **Ship Date:** \_\_\_\_\_  
**ESO #:** \_\_\_\_\_ **DBS Work Order #:** \_\_\_\_\_ **No. of Packages:** \_\_\_\_\_  
**Inspected By:** \_\_\_\_\_  
**Tech Name:** \_\_\_\_\_

Initial each item, comment as necessary:

**Lubrication:**  
Check all connections \_\_\_\_\_  
Check oil level \_\_\_\_\_  
Check protection switch \_\_\_\_\_

**Fuel:**  
Check all connections (leaks, etc.) \_\_\_\_\_  
Check throttle and governor linkages \_\_\_\_\_

**Air:**  
Check air filter pipework \_\_\_\_\_  
Check vent piping and connections \_\_\_\_\_  
Check air flap and solenoid (if fitted) \_\_\_\_\_

**Water:**  
Check and adjust fan belts \_\_\_\_\_  
Check anti-freeze concentration & pH level \_\_\_\_\_  
Check remote fans and pumps (if applicable) \_\_\_\_\_  
Check radiator core and tanks (leaks, etc.) \_\_\_\_\_  
Check protection switch \_\_\_\_\_

**DC:**  
Check and adjust alternator belts \_\_\_\_\_  
Check acid level of batter(s) (top-up as necessary) \_\_\_\_\_  
Check condition of lugs and terminals \_\_\_\_\_

**AC:**  
Visually inspect windings \_\_\_\_\_  
Check power connections \_\_\_\_\_  
Check circuit breaker and connections \_\_\_\_\_  
Check contactor panel connections and lamps \_\_\_\_\_

**Heater:** (if fitted)  
Check hose connections \_\_\_\_\_  
Check operation \_\_\_\_\_

**Off Load Test:**  
Oil Pressure \_\_\_\_\_ PSI      Water Temperature \_\_\_\_\_ F  
Battery Charging Volts \_\_\_\_\_ VDC      AC Voltage \_\_\_\_\_ VAC  
Frequency \_\_\_\_\_ Hz      Engine Speed \_\_\_\_\_ RPM

Other: \_\_\_\_\_

**Silencer:**  
Check system for fumes \_\_\_\_\_

Comments \_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_